

## Wall Mount Installation Sample P3.9 and P2.5

Screen Size	136.5" x 78"
Cabinet size	19.5" Width x 37.5" Height
Matrix	7 Col x 2 Row ( 14 Cabinets)
Resolution	P3.9 896 x 512 Pixels

This is an example of a Video Wall installed over a flat wooden surface. You will need to have the wooden base constructed and mounted by your local contractor prior to Video Wall installation. The wooden base needs to match the exact measurements of the screen. In this example, the surface was very even, so no struts were necessary, however, if your surface is uneven, struts may be necessary.



The cabinets will be mounted using lag screws, and the cabinets will be secured to one another using 3/8" nuts and bolts



Hardware		
Part Number	Description	Qty
CFSP3.920x40I	Indoor 3800 Hz Led Cabinet	14
5/16 1-1/2 in	Lag Screws	56
1/4 1"	Flat washer	56
3/8 1"	Nut and Bolt	28

